

PRINCE GEORGE'S COUNTY  
HISTORIC SITE SUMMARY SHEET

Survey #: P.G. #76B-9 Building Date: ca. 1830's  
Building Name: Sheriff-Mattingly House  
Location: 1011 Lindsay Road, Oxon Hill, Maryland

Private/Residence/Occupied/Excellent/Inaccessible

Description:

The Sheriff-Mattingly house is an imposing three-part brick structure, presently surrounded by the small lots of a 1950's subdivision just outside the Capital Beltway near Oxon Hill. The central block is a two-and-one-half-story gable-roofed building (ca. 30 feet square) with principal facade to the north. (Two flanking two-story wings have been attached during this century.) Entrance is in the central (but off-center) bay of the three-bay north facade, through a panelled door with seven-pane transom and three-pane sidelights. The doorway is surmounted by a flat arch, as are the window openings. Across the north facade runs a one-story porch, supported by four Tuscan columns, built early in this century. Ghosts of earlier pilasters are visible on each side of the door. The walls of the house are laid in common bond: one header to five stretchers. Windows on the first story are 9/6, and 6/6 on the second; they are double hung sash, but only the lower sash is movable. The boxed cornice is returned at the gable ends. Two projecting courses of brick corbelling provide a decorative border below the cornice. There is an interior chimney at each of the east and west gable ends, to the rear (south) of the ridge. The east (kitchen and dining) wing was built in 1920, and replaces the original one-story kitchen wing. The west, (sitting-room) wing was built new in 1929. In both wings, bricks were selected to match the color and size of those in the main block, and care was taken to reproduce the corbelled brick cornice.

Significance:

The Sheriff-Mattingly house is one of only a handful of late-Federal brick plantation houses surviving in Prince George's County. Construction details indicate that it was built in the 1830's or 1840's during the ownership of Ann Talbott, who received this farm (Hart Park, part of Oxon Hill Manor) from her uncle. From 1853 until his death in 1897, this house was the home of Alfred Thomas Sheriff, who called it "Melrose", and left it to his daughter, Mary Seltzer. For much of the early twentieth century, it was the home of Circuit Court Judge Joseph C. Mattingly, who built the two flanking wings in the 1920's. After Mattingly's death, the property was sold to a developer, who laid out the subdivision of Southlawn, reserving the largest lot for the old house. Today this imposing house is framed by large oak trees which give a hint of its historic setting, and, although surrounded by subdivision housing, is an important and unusual landmark.

Acreage: 40,839 square feet.

# Maryland Historical Trust State Historic Sites Inventory Form

Survey No. P.G. #76B-9

Magi No.

DOE ☐ yes ☐ no

## 1. Name (indicate preferred name)

historic Melrose, Hart Park (See note, item #8)

and/or common Sheriff - Mattingly House

## 2. Location

street & number 1011 Lindsay Road ☐ not for publicationcity, town Oxon Hill ☐ vicinity of congressional district 4th

state Md. 20021 county Prince George's

## 3. Classification

Category	Ownership	Status	Present Use	
<input type="checkbox"/> district	<input type="checkbox"/> public	<input checked="" type="checkbox"/> occupied	<input type="checkbox"/> agriculture	<input type="checkbox"/> museum
<input checked="" type="checkbox"/> building(s)	<input checked="" type="checkbox"/> private	<input type="checkbox"/> unoccupied	<input type="checkbox"/> commercial	<input type="checkbox"/> park
<input type="checkbox"/> structure	<input type="checkbox"/> both	<input type="checkbox"/> work in progress	<input type="checkbox"/> educational	<input checked="" type="checkbox"/> private residence
<input type="checkbox"/> site	<b>Public Acquisition</b>	<b>Accessible</b>	<input type="checkbox"/> entertainment	<input type="checkbox"/> religious
<input type="checkbox"/> object	<input type="checkbox"/> in process	<input type="checkbox"/> yes: restricted	<input type="checkbox"/> government	<input type="checkbox"/> scientific
	<input checked="" type="checkbox"/> being considered	<input type="checkbox"/> yes: unrestricted	<input type="checkbox"/> industrial	<input type="checkbox"/> transportation
	<input type="checkbox"/> not applicable	<input checked="" type="checkbox"/> no	<input type="checkbox"/> military	<input type="checkbox"/> other:

## 4. Owner of Property (give names and mailing addresses of all owners)

name Kenneth Fisher Jr.

street &amp; number 1011 Lindsay Road telephone no.: 567-6085

city, town Oxon Hill state and zip code Md. 20021

## 5. Location of Legal Description

courthouse, registry of deeds, etc. P.G. County Court House liber 4367

street &amp; number Main Street folio 385

city, town Upper Marlboro state Md.

## 6. Representation in Existing Historical Surveys

title P.G. Co. Inventory of Historic Sites

date 1974 ☐ federal ☐ state ☒ county ☐ local

depository for survey records History Division, MNCPPC

city, town Riverdale state Md.

## 7. Description

Survey No. P.G. #76B-9

Condition  
☒ excellent  
☐ good  
☐ fair

☐ deteriorated  
☐ ruins  
☐ unexposed

Check one  
☐ unaltered  
☒ altered

Check one  
☒ original site  
☐ moved      date of move \_\_\_\_\_

Prepare both a summary paragraph and a general description of the resource and its various elements as it exists today.

The Sheriff-Mattingly house is an imposing three-part brick structure, presently surrounded by the small lots of a 1950's subdivision just outside the Capital Beltway near Oxon Hill. The central block is a two-and-one-half-story gable-roofed building (ca. 30 feet square) with principal facade to the north. (Two flanking two-story wings have been attached during this century.) Entrance is in the central (but off-center) bay of the three-bay north facade, through a panelled door with seven-pane transom and three-pane sidelights. The doorway is surmounted by a flat arch, as are the window openings. Across the north facade runs a one-story porch, supported by four Tuscan columns, built early in this century. Ghosts of earlier pilasters are visible on each side of the door.

The walls of the house are laid in common bond: one header to five stretchers. Windows on the first story are 9/6, and 6/6 on the second; they are double hung sash, but only the lower sash is movable. There are louvered shutters at the windows in the north (main) facade. The boxed cornice is returned at the gable ends. Two projecting courses of brick corbelling provide a decorative border below the cornice. There is an interior chimney at each of the east and west gable ends, to the rear (south) of the ridge.

In plan, the central (original) block is divided into four asymmetrical sections, the two larger spaces being on the west side. Only the two rear (south) parlors have fireplaces; both mantels are replacements. A third mantel has been placed against the west wall of the entry-hall (northeast space), creating a false fireplace. The fourth section is composed of staircase and utility space (now a bathroom). The stair rises to the north, then turns west over the entrance doorway, covering a small triangle of the door space. The stair has a handsome turned newel post, and plain balusters, square in section. The architrave trim of doors and windows has cyma reversa molding.

The roof structure of this main block is formed from hand-hewn rafters, joined in barefaced tenon. There is no ridgeboard. Midway along the rafters are tie-beams joined to the rafters by dovetail halving.

The east (kitchen and dining) wing was built in 1920, and replaces the original one-story kitchen wing. The west (sitting-room) wing was built new in 1929. In both wings, bricks were selected to match the color and size of those in the main block, and care was taken to reproduce the corbelled brick cornice.

## 8. Significance

Survey No. P.G. #76B-9

Period	Areas of Significance—Check and justify below			
<input type="checkbox"/> prehistoric	<input type="checkbox"/> archeology-prehistoric	<input type="checkbox"/> community planning	<input type="checkbox"/> landscape architecture	<input type="checkbox"/> religion
<input type="checkbox"/> 1400-1499	<input type="checkbox"/> archeology-historic	<input type="checkbox"/> conservation	<input type="checkbox"/> law	<input type="checkbox"/> science
<input type="checkbox"/> 1500-1599	<input type="checkbox"/> agriculture	<input type="checkbox"/> economics	<input type="checkbox"/> literature	<input type="checkbox"/> sculpture
<input type="checkbox"/> 1600-1699	<input checked="" type="checkbox"/> architecture	<input type="checkbox"/> education	<input type="checkbox"/> military	<input type="checkbox"/> social/
<input type="checkbox"/> 1700-1799	<input type="checkbox"/> art	<input type="checkbox"/> engineering	<input type="checkbox"/> music	<input type="checkbox"/> humanitarian
<input checked="" type="checkbox"/> 1800-1899	<input type="checkbox"/> commerce	<input type="checkbox"/> exploration/settlement	<input type="checkbox"/> philosophy	<input type="checkbox"/> theater
<input type="checkbox"/> 1900-	<input type="checkbox"/> communications	<input type="checkbox"/> industry	<input type="checkbox"/> politics/government	<input type="checkbox"/> transportation
		<input type="checkbox"/> invention		<input checked="" type="checkbox"/> other (specify) local history

Specific dates ca.1830-1840

Builder/Architect

check: Applicable Criteria: ☐ A ☐ B ☐ C ☐ D  
and/or

Applicable Exception: ☐ A ☐ B ☐ C ☐ D ☐ E ☐ F ☐ G

Level of Significance: ☐ national ☐ state ☐ local

Prepare both a summary paragraph of significance and a general statement of history and support.

The Sheriff-Mattingly house is very significant in that it is one of only a handful of late-Federal brick plantation homes surviving in Prince George's County. All that remains of its original setting is a nearly-one-acre lot, surrounded by the small lots of a 1950's subdivision known as Southlawn.

The farm in which this dwelling stands has been known by many names through its history: Hart Park, then part of Oxon Hill Manor (which incorporated several other tracts in addition to Hart Park), and Melrose.<sup>1</sup> Construction details strongly suggest that the central block of the house was built in the 1830's or 1840's, during the ownership of Ann Talbott; she and her children had received 99 acres of Oxon Hill Manor (Hart Park) as a gift from her uncle. In 1853, Ann Talbott and her children sold the house and approximately sixty acres to Alfred Thomas Sheriff, and it became the Sheriff family home from then until his death in 1897. (It was during Sheriff's tenure that the home place was known as "Melrose".) After Sheriff's death, the house and 18 acres passed to his daughter, Mary Sheriff Seltzer, who referred to her farm home by its oldest name, Hart Park.<sup>2</sup>

In 1918, the old house was purchased by the Mattingly family and became the home of Circuit Court Judge Joseph C. Mattingly until his death in 1948. Judge Mattingly bought up adjoining lands, thus creating a working farm of ca. 250 acres. In 1920 he built the new (east) kitchen wing on the foundations of an earlier kitchen. In 1929 he added a balancing (but unequal) sitting-room wing on the west, resulting in a large and imposing three-part house. In the construction of the wings, Mattingley reused bricks from historic structures, and took care to reproduce the corbelled cornice of the main block.<sup>3</sup>

## 9. Major Bibliographical References

Survey No. P.G.#76B-9

See chain of title  
See Notes, Item #8  
Interview with owner, December 1984

## 10. Geographical Data

Acreage of nominated property 40,839 sq. ft.

Quadrangle name Anacostia quadrangle, Section D

Quadrangle scale

UTM References do NOT complete UTM references

A 

--	--	--	--	--	--	--	--	--	--

  
Zone Easting Northing

B 

--	--	--	--	--	--	--	--	--	--

  
Zone Easting Northing

C 

--	--	--	--	--	--	--	--	--	--

D 

--	--	--	--	--	--	--	--	--	--

E 

--	--	--	--	--	--	--	--	--	--

F 

--	--	--	--	--	--	--	--	--	--

G 

--	--	--	--	--	--	--	--	--	--

H 

--	--	--	--	--	--	--	--	--	--

Verbal boundary description and justification

List all states and counties for properties overlapping state or county boundaries

state	code	county	code
-------	------	--------	------

state	code	county	code
-------	------	--------	------

## 11. Form Prepared By

name/title Susan G. Pearl, Research Historian

organization Historic Preservation Commission

date February 1985

street &amp; number c/o County Planning MNCPPC

telephone 952-3521

city or town Upper Marlboro

state Md.

The Maryland Historic Sites Inventory was officially created by an Act of the Maryland Legislature to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 supplement.

The survey and inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.

return to: Maryland Historical Trust  
Shaw House  
21 State Circle  
Annapolis, Maryland 21401  
(301) 269-2438

## 7 (Continued)

In the late 1950's, the subdivision of Southlawn was built around the Sheriff house, and just short of an acre was retained around the house as the largest of the residential lots. The house is located ca. 200 feet in from the road and is only partially visible from it, framed by several large oaks. There are two modern storage buildings in the yard behind the house.

## 8 (Continued)

After Judge Mattingly's death, his heirs sold the property to a developer, who laid out the subdivision of Southlawn, reserving the largest lot for the old house.<sup>4</sup> Today, this imposing house is framed by large oak trees, giving a hint of its historic setting, and, although surrounded by subdivision housing, is an important and unusual landmark.

Notes

1 Patented certificate #1043 (Hart Park), #1590 (Oxon Hill Manor); Prince George's County Tax Assessments.

2 Prince George's County Deeds, AR#4:597; ON#1:504,648; JWR#41:301; JB#1:226; Equity #2437; Prince George's County Tax Assessments 1861-1871, 1888-1900.

3 Site inspection and interview with owner, December 1985.

4 Prince George's County Deed, #2067:312; Plat WWW#31:41.

\* Note:

This property is listed on the Prince George's Inventory as "Greenwood", based on confusion with an adjoining tract (another part of Oxon Hill Manor) on which stood the rectory of St. Barnabas Church. That property was known as Greenwood; the building no longer stands.

MARYLAND HISTORICAL TRUST WORKSHEET

1762455504

NOMINATION FORM  
for the  
NATIONAL REGISTER OF HISTORIC PLACES, NATIONAL PARKS SERVICE

SEE INSTRUCTIONS

<b>1. NAME</b>				
COMMON:				
AND/OR HISTORIC: Greenwood				
<b>2. LOCATION</b>				
STREET AND NUMBER: 1011 Lindsey Road				
CITY OR TOWN: Oxon Hill				
STATE: Maryland		COUNTY: Prince George's		
<b>3. CLASSIFICATION</b>				
<b>CATEGORY</b> (Check One)	<b>OWNERSHIP</b>		<b>STATUS</b>	<b>ACCESSIBLE TO THE PUBLIC</b>
<input type="checkbox"/> District <input checked="" type="checkbox"/> Building <input type="checkbox"/> Site <input type="checkbox"/> Structure <input type="checkbox"/> Object	<input type="checkbox"/> Public            Public Acquisition: <input checked="" type="checkbox"/> Private <input type="checkbox"/> In Process <input type="checkbox"/> Bath <input type="checkbox"/> Being Considered		<input checked="" type="checkbox"/> Occupied <input type="checkbox"/> Unoccupied <input type="checkbox"/> Preservation work in progress	Yes: <input type="checkbox"/> Restricted <input type="checkbox"/> Unrestricted <input checked="" type="checkbox"/> No
PRESENT USE (Check One or More as Appropriate)				
<input type="checkbox"/> Agricultural <input type="checkbox"/> Commercial <input type="checkbox"/> Educational <input type="checkbox"/> Entertainment	<input type="checkbox"/> Government <input type="checkbox"/> Industrial <input type="checkbox"/> Military <input type="checkbox"/> Museum	<input type="checkbox"/> Park <input checked="" type="checkbox"/> Private Residence <input type="checkbox"/> Religious <input type="checkbox"/> Scientific	<input type="checkbox"/> Transportation <input type="checkbox"/> Other (Specify) _____	<input type="checkbox"/> Comments _____
<b>4. OWNER OF PROPERTY</b>				
OWNER'S NAME: Donald Funk				
STREET AND NUMBER:				
CITY OR TOWN: Hagerstown			STATE: Maryland	
<b>5. LOCATION OF LEGAL DESCRIPTION</b>				
COURTHOUSE, REGISTRY OF DEEDS, ETC: Prince George's County Courthouse				
STREET AND NUMBER:				
CITY OR TOWN: Upper Marlboro			STATE: Maryland	
Title Reference of Current Deed (Book & Pg. #):				
<b>6. REPRESENTATION IN EXISTING SURVEYS</b>				
TITLE OF SURVEY: None				
DATE OF SURVEY: <input type="checkbox"/> Federal <input type="checkbox"/> State <input type="checkbox"/> County <input type="checkbox"/> Local				
DEPOSITORY FOR SURVEY RECORDS:				
STREET AND NUMBER:				
CITY OR TOWN:			STATE:	



## 7. DESCRIPTION

CONDITION	(Check One)					
	<input type="checkbox"/> Excellent	<input checked="" type="checkbox"/> Good	<input type="checkbox"/> Fair	<input type="checkbox"/> Deteriorated	<input type="checkbox"/> Ruins	<input type="checkbox"/> Unexposed
	(Check One)			(Check One)		
	<input checked="" type="checkbox"/> Altered	<input type="checkbox"/> Unaltered	<input type="checkbox"/> Moved	<input checked="" type="checkbox"/> Original Site		
DESCRIBE THE PRESENT AND ORIGINAL (if known) PHYSICAL APPEARANCE						
<p>The house is a two story brick structure with a three bay main (north) facade. It is laid up in common bond throughout. The central doorway has transom and sidelights. The cornice, returning into the gable ends, is boxed. The flush gable end chimneys are positioned to the south of the roof ridge. Windows are double hung sash, 9/6 on the first floor and 6/6 on the second, with modern mullions.</p> <p>Lower two story wings have been added on either end. The one to the east dates about twenty years after the main block; the one to the west is 20th century.</p> <p>A one story porch with columns has been added across the main facade.</p>						

SEE INSTRUCTIONS

**8. SIGNIFICANCE****PERIOD (Check One or More as Appropriate)**☐ Pre-Columbian☐ 16th Century☐ 18th Century☐ 20th Century☐ 15th Century☐ 17th Century☒ 19th Century**SPECIFIC DATE(S) (If Applicable and Known)**

c. 1840, c. 1860

**AREAS OF SIGNIFICANCE (Check One or More as Appropriate)**

Aboriginal

☐ Education☐ Political☐ Urban Planning☐ Prehistoric☐ Engineering☐ Religion/Phi-☐ Other (Specify)☐ Historic☐ Industry

losophy

☐ Agriculture☐ Invention☐ Science☐ Architecture☐ Landscape☐ Sculpture☐ Art☐ Architecture☐ Social/Human-☐ Commerce☐ Literature

itorion

☐ Communications☐ Military☐ Theater☐ Conservation☐ Music☐ Transportation**STATEMENT OF SIGNIFICANCE**

SEE INSTRUCTIONS

## 9. MAJOR BIBLIOGRAPHICAL REFERENCES

## 10. GEOGRAPHICAL DATA

LATITUDE AND LONGITUDE COORDINATES DEFINING A RECTANGLE LOCATING THE PROPERTY			O R	LATITUDE AND LONGITUDE COORDINATES DEFINING THE CENTER POINT OF A PROPERTY OF LESS THAN TEN ACRES		
CORNER	LATITUDE	LONGITUDE		LATITUDE	LONGITUDE	
	Degrees Minutes Seconds	Degrees Minutes Seconds		Degrees Minutes Seconds	Degrees Minutes Seconds	
NW	° ' "	° ' "		° ' "	° ' "	
NE	° ' "	° ' "		° ' "	° ' "	
SE	° ' "	° ' "		° ' "	° ' "	
SW	° ' "	° ' "		° ' "	° ' "	

APPROXIMATE ACREAGE OF NOMINATED PROPERTY:

Acreage Justification:

LIST ALL STATES AND COUNTIES FOR PROPERTIES OVERLAPPING STATE OR COUNTY BOUNDARIES

STATE:		COUNTY:	
STATE:		COUNTY:	
STATE:		COUNTY:	
STATE:		COUNTY:	

## 11. FORM PREPARED BY

NAME AND TITLE: Christopher Owens, Park Historian	
ORGANIZATION MNCPPC	DATE 20 Nov 73
STREET AND NUMBER: 8787 Georgia Avenue	
CITY OR TOWN: Silver Spring	STATE Maryland

## 12.

State Liaison Officer Review: (Office Use Only)

Significance of this property is:


National ☐ State ☐ Local ☐

Signature

SEE INSTRUCTIONS


Sitting Room Wing

New 1929



1" = 6'

Not exactly to scale



Kitchen Wing  
1920

Built on old kitchen  
foundations

P.G. #76 B-9

Sheriff house  
(Hart Park)

Chain of Title

Sheriff House  
P.G. #76B-9

#4367:385 17 May 1974 Deed	Donald and Eleanor Funk to Kenneth and Betty Jane Fisher; Lot #1 in Block 0 of Southlawn, as in plat WWW 31:41; which grantor acquired by #2922:394.
#2922:394 2 Jan. 1964 Deed	Herbert E. Hurley and George Huguely, Jr., trustees under Deed of Trust, 31 December 1963 to Donald and Eleanor Funk; Lot #11 in Block 0, Southlawn.
#2922:392 31 Dec. 1963 Deed of Trust	Louis Dismar and Julius Maedel, trustees under Deed of Trust #2339:32, to H. Hurley and G. Huguely Jr.; Lot #11 in Block 0, Southlawn.
#2339:32 8 June 1959 Deed of Trust	Clark and Geraldine Brubaker to Dismar and Maedel, trustees; Lot #11 in Block 0, Southlawn.
#2339:31 8 June 1959 Deed	Michael Capacchione et ux to Clark and Geraldine Brubaker; Lot #11 in Block 0, Southlawn, as per plat WWW #31:41.
(WWW #31:41 29 Nov. 1957 Plat)	Plan of Southlawn subdivision; total acreage 8.8998 acres; Lot #11 in Block 0 is 40,839 square feet.
#2067:312 5 Dec. 1956 Deed	Eleanor Stouffer and Joseph C. Mattingly, Jr. et al (.8 heirs of late Judge Mattingly) to Michael Capacchione; land which the late Joseph C. Mattingly acquired by #365:149, 8.9 acres.
#365:149 9 Jan. 1931 Deed	Harriet Mattingly to Joseph C. Mattingly, land which grantor acquired by #137:146, 18 acres part of Oxon Hill Manor, part of land of which A.T. Sheriff died possessed.
#137:146 10 Oct. 1918 Deed	William and Emily Streater to Harriet Mattingly; 18 acres, part of Oxon Hill Manor, which grantor acquired by #72:430.
#72:430 4 Nov. 1911 Deed	Mary F. and John M. Seltzer to William Streater; part of Oxon Hill Manor which Seltzer acquired by JWB #41:301 and JB #1:226.

- 2 -

JB #1:226  
2 March 1898  
Deed

Henry E. Sheriff to Mary F. Seltzer; 18 acres and 30 perches of Oxon Hill Manor; by decree of Court of Equity (#2437), Henry E. Sheriff appointed trustee to convey property of Charles C. Whittington, on which A.T. Sheriff died, being Whittington's 1/12 interest.

JWB #41:301  
21 July 1897  
Deed

Henry E. Sheriff et al to Mary F. Sheriff Seltzer; 18 acres of Oxon Hill Manor; A.T. Sheriff deeded to Henry E. Sheriff 20 acres of Oxon Hill Manor, and willed 20 other acres of Oxon Hill Manor to his grandchildren, and willed 6 other acres of Oxon Hill Manor to his grandson Thomas Sheriff; leaving 18 acres of Oxon Hill Manor (on which old house stands where Alfred Thomas Sheriff resided) undisposed of and which he intended to give to his daughter Mary F. Seltzer, his only child not provided for, but died before so devising; therefore, grantors convey all of their interest in these 18 acres of Oxon Hill Manor to Mary F. Seltzer.

#2437  
24 Feb. 1898  
Equity

Henry E. Sheriff appointed trustee to sell undivided property of Alfred Thomas Sheriff, which he acquired by ON #1:648. (Testimony indicates that the 18 acre 30 perch property has on it a building valued at \$900.)

ON #1:648  
10 May 1854  
Deed of Partition

John and Mary Martin, and Thomas and Cloe Sheriff, division of land which Martin and Sheriff acquired by ON #1:504. Sheriff to receive 54 acres, 1 rod, and 30 perches; Martin to receive 44-3/4 acres.

ON #1:504  
29 Sept. 1853  
Deed

Ann Talbott of P.G. County, John Davidson of D.C., Francis Kirby Davidson of Alexandria, Zachariah and Elizabeth Whitmore of Tennessee, and Ann Eliza Davidson of P.G. County to John Martin and Thomas Sheriff (for \$1000); 99 acres and 30 perches of Oxon Hill Manor lying between and adjoining the lands of Mrs. Christiana Edelen and Dr. John H. Bayne.

AB #4:597  
19 Sept. 1827  
Deed

John Baptiste Kerbey of D.C. to Ann Talbott, his niece, and her four children (J.B. Davidson, F.K. Davidson, Elizabeth Davidson, and Ann Eliza Davidson), 99 acres and 30 perches, part of Oxon Hill Manor; for their better maintenance and support, livelihood and preferment; for Ann Talbott's lifetime and after her death to her four said children.







P.G. #76B-9

Sheriff-Mattingley House  
Prince George's County, MD.  
Susan G. Pearl  
December 1985  
North elevation  
Neg: Md. Hist. Trust, Annapolis, MD.



P.G. #76B-9

Sheriff-Mattingley House  
Prince George's County, MD.

Susan G. Pearl

December 1984

Southeast 3/4 elevation

Neg: Md. Hist. Trust, Annapolis, MD.



NAME GREENWOOD #76B-9

LOCATION 1011 LINDSAY ~~Bd~~ OXON HILL, Md

FACADE N

PHOTO TAKEN 11/20/73 MDWYER



P.G. #76B-9

Sheriff-Mattingly House  
Prince George's County, MD.  
Susan G. Pearl  
December 1984  
North entrance  
Neg: Md. Hist. Trust, Annapolis, MD.